



Ashghal – 3 Schools At Wakrah

Description:

The work comprises of the construction of, completion and maintenance of three new schools:

School: 17/20 – Elementary Girls School (PIN-90041182)

School: 18/20 – Preparatory Girls School (PIN-90041183)

School: 17/20 – Preparatory Model School (PIN-90041184)

Scope of Work:

- The works for each school consisted of, but were not limited to, School Building, Assembly Hall, Auditorium, Guard Room, Service Yard and Substation, Sports Courts, Paving, Landscaping, Shaded Structures, Parking and Boundary wall including External services infrastructures
- The new buildings are reinforced concrete with block work infill. The assembly and Multipurpose Halls are covered with structural steel structure and roof cladding system with approximately 10,000 m². overall built up area per school

Key Facts

Client	Public Works Authority
Start Date	October 2010
Completion Date	February 2013
Project Value	QR 162 Million

